

Engineer's Official Bid Form - Kexon Drive Extension (Revised 02-14-2022)

Item	ODOT CMS Item	Description	Unit	Quantity	Unit Price	Estimated Cost
SANITARY						
1	611	8" PVC SANITARY SEWER, TYPE C	LIN FT	887		
2	611	10" PVC SANITARY SEWER, TYPE C	LIN FT	3013		
3	611	SANITARY MANHOLE, 4' DIAMETER	EACH	13		
DRAINAGE						
4	611	STANDARD NO. 3 STORM SEWER MANHOLE	EACH	12		
5	611	NO. 2-2-B STORM CATCH BASIN	EACH	3		
6	611	NO. 3A MODIFIED STORM CATCH BASIN	EACH	16		
7	611	HEADWALL	EACH	1		
8	611	12" STORM SEWER, TYPE C	LIN FT	32		
9	611	12" STORM SEWER, TYPE B	LIN FT	725		
10	611	15 STORM SEWER, TYPE B	LIN FT	672		
11	611	18" STORM SEWER, TYPE B	LIN FT	1067		
12	611	24" STORM SEWER, TYPE B	LIN FT	344		
13	611	24" STORM SEWER, TYPE C	LIN FT	336		
14	SPECIAL	STORM TAP	EACH	1		
15	SPECIAL	DITCH CLEANING	LIN FT	250		

PAVEMENT						
16	201	CLEARING AND GRUBBING (INCLUDES REMOVAL OF OBSTRUCTIONS PER ITEM 202)	LUMP	1		
17	203	EXCAVATION INCLUDING EMBANKMENT	LUMP	1		
18		SUB-GRADE COMPACTION & PROOF ROLLING	SQ YD	10694		
19	304	AGGREGATE BASE, 12" THICK	CU YD	3406		
20	407	TACK COAT, 0.1 GAL/SQ YD	GAL	455		
21	408	BITUMINOUS PRIME COAT, 0.35 GAL/SQ YD	GAL	1594		
22	448	ASPHALT CONCRETE INTERMEDIATE COURSE TYPE 2, PG64-22, 2-1/2"	CU YD	316		
23	448	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 1-1/2"	CU YD	190		
24	255	FULL DEPTH PAVEMENT REMOVAL & RIGID REPLACEMENT, CLASS C	SQ YD	4649		
25	605	6" UNDERDRAINS	LIN FT	5370		
26		CONCRETE CURB & GUTTER, TYPE 2	LIN FT	5370		
27	SPECIAL	TENSAR GEOTEXTILE GRID, BX1200	SQ YD	10694		
28	712	ODOT TYPE D WOVEN SUBGRADE FABRIC	SQ YD	10694		
29	651	TOPSOIL STOCKPILED, AS PER PLAN	CU YD	6318		
30	652	PLACING STOCKPILED TOPSOIL, AS PER PLAN	CU YD	1792		
31	511	CONCRETE DRIVE REPAIR	SQ FT	1493		
MISCELLANEOUS						
32	611	4" TO 15" CONDUIT (TILE) REPAIR-TO BE USED AS DIRECTED BY ENGINEER	LIN FT	200		
33	611	LARGER THAN 15" CONDUIT (TILE) REPAIR-TO BE USED AS DIRECTED BY ENGINEER	LIN FT	100		
34	614	MAINTENANCE OF TRAFFIC	LUMP	1		
35	623	CONSTRUCTION LAYOUT STAKING	LUMP	1		
36	624	MOBILIZATION	LUMP	1		
EROSION CONTROL						
37	659	FERTILIZER	TON	0.8		
38	659	SEEDING AND MULCHING, CLASS 1 LAWN MIXTURE	SQ YD	8902		
39	659	TEMPORARY EROSION CONTROL SEED, CLASS 7 MIXTURE	SQ YD	1000		
40	832	DANDI BAG AT CATCH BASIN, AS PER PLAN	EACH	19		
41	832	SILT FENCE, AS PER PLAN	LIN FT	1000		
TOTAL UNIT PRICE BID						
ALTERNATE 1			NA	NA	\$119,125.80	
ALTERNATE 2			LUMP	1		