

**Engineer's Official Bid Form - Clark Street Sanitary Sewer Extension and Pump Station**

Item	ODOT CMS Item	Description	Unit	Quantity	Unit Price	Estimated Cost
<b>SANITARY</b>						
1	611	8" PVC SANITARY SEWER, TYPE B	LIN FT	400		
2	612	8" PVC SANITARY SEWER, TYPE C	LIN FT	972		
3	612	4" RJ-900 CERTA-LOK DR-18 SANITARY SEWER FORCE MAIN, DIRECTIONAL BORED	LIN FT	370		
4	611	SANITARY MANHOLE, 4' DIAMETER	EACH	4		
5	611	SANITARY PUMP STATION	EACH	1		
6	0	CHAIN LINK FENCE (INCLUDING GATE AND RAZOR WIRE)	LIN FT	100		
7	0	EMERGENCY GENERATOR ( INCLUDING HOOKUP AND FOUNDATION)	EACH	1		
<b>MISCELLANEOUS</b>						
10	611	4" TO 15" CONDUIT (TILE) REPAIR-TO BE USED AS DIRECTED BY ENGINEER	LIN FT	300		
11	611	LARGER THAN 15" CONDUIT (TILE) REPAIR-TO BE USED AS DIRECTED BY ENGINEER	LIN FT	50		
12	614	MAINTENANCE OF TRAFFIC	LUMP	1		
13	623	CONSTRUCTION LAYOUT STAKING	LUMP	1		
14	624	MOBILIZATION	LUMP	1		
15	204	EXCAVATION AND EMBANKMENT	LUMP	1		
16	651	TOPSOIL STOCKPILED, AS PER PLAN	CU YD	260		
17	652	PLACING STOCKPILED TOPSOIL, AS PER PLAN	CU YD	260		
18	SPECIAL	CONCRETE DRIVE REMOVAL-INCLUDING SAW CUTTING	SQ FT	1937		
19	511	CONCRETE DRIVE REPAIR	SQ FT	2271		
20	SPECIAL	STONE DRIVE REPAIR	SQ FT	821		
21	0	ASPHALT ROAD REPAIR	SQ FT	100		
22	0	CURB REMOVAL AND REPAIR	SQ FT	10		
23	0	CURB CUT FOR DRIVEWAY	LIN FT	45		
<b>EROSION CONTROL</b>						
26	659	FERTILIZER	TON	0		
27	659	SEEDING AND MULCHING, CLASS 1 LAWN MIXTURE	SQ YD	2405		
28	659	TEMPORARY EROSION CONTROL SEED, CLASS 7 MIXTURE	SQ YD	100		
29	832	SILT FENCE, AS PER PLAN	LIN FT	1000		
<b>TOTAL UNIT PRICE BID</b>						