

WILLIAMS COUNTY FAIRGROUNDS GOAT BARN

MONTPELIER, OHIO

PRE-BID QUESTIONS AND RESPONSES

Number	Date	Bidder	Question	Response
1	4/17/2017	Siebenaler Construction	Are the poles at the overhead doors to be wrapped?	Please use an extended J-channel to cover any of the exposed treated pole.
2	4/19/2017	Siebenaler Construction	What type of bolt material is to be used?	Galvanized fasteners are to be used when in contact with the treated lumber.
3	4/19/2017	Siebenaler Construction	Are the doors required to be insulated?	No, all of the doors are to be non-insulated steel.
4	4/20/2017	Siebenaler Construction	Will dirt spoils need to be hauled off site, or is there a place on-site to dispose of them?	The spoils can be disposed on the fairgrounds property either north or south of the river. An exact location will be determined by the Owner at the time of construction.
5	4/20/2017	Siebenaler Construction	What type of granular backfill is to be used?	Bank run gravel.
6	4/20/2017	Siebenaler Construction	Is the top of the granular backfill assumed to be the finish floor elevation for the base bid? And the top of the concrete assumed to be the finish floor elevation for the Bid Alternate #1?	Yes. In the case of bid alternate #1, the top of the granular fill and the top of the concrete shall be level.
7	4/21/2017	-	-	(6) Emergency Lights are to be attached to pendants and suspended from the bottom chord of the trusses. Refer to attached Sheet E1.1 for details.
8	4/21/2017	Owen's Electric	I didn't see any exterior lighting, just checking that it is supposed to be that way.	There is enough existing site lighting that no exterior lighting is to be provided on the building.
NO FURTHER QUESTIONS WILL BE RESPONDED TO PRIOR TO THE BID OPENING				